

MSME DEVELOPMENT INSTITUTE

Opp. Konkan Railway Station
Quepem Road
Margao-Goa

TENDER NOTICE

Dated: 16-11-2011

No. MSME-DI/MAO/D-39011/1/2011-12

The Director, MSME Development Institute (Government of India, Ministry of MSME), Margao-Goa, invites on behalf of Govt. of India, Min. of MSME, sealed Item Rate Tender from the eligible contractors registered in appropriate Class and Categories for the work as detailed under:

Sl. No.	Name of Work	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Document (in Rs.)	Class and Category of Contractor	Time Allowed
1	Electrification of Mechanical Workshop as per the details in Tender Documents	5,00,000/-	5,000/-	500/- (non-refundable)	Appropriate class	45 days
	Date & Time for application for issue of tender form	i) Last date & time of receipt of application 02-12-2011 ii) Last date of issue of Tender Documents 09-12-2011				
	Time/Date of receipt/issue of tender	iii) Last date and time of duly filled tender document is upto 3.00 pm on 15-12-2011 iv) The Tender will be opened at 3.30 pm on 15-12-2011 in the office of the MSME Development Institute.				

TERMS AND CONDITIONS

The application of the intending tenderers should accompany the following documents.

- 1) Attested copy of valid Registration Certificate of appropriate class with 33 K.V. Electrical Contract License.
- 2) Attested copy of PAN Card
- 3) Two separate demand draft/pay order for the cost of tender document and Earnest Money Deposit, drawn on any Nationalized/Scheduled Bank in the favour of the Director, MSME-DI, Margao-Goa.
- 4) The applicant should submit the declaration giving the names of the works in hand in the above mentioned category, if any.
- 5) The Demand Draft of EMD amount will be returned to unsuccessful bidder.
- 6) The payment will be made only after completion of work and the work approval from concerned Engineer Incharge/authority and issue of test certificate as per G.E.O. work.

Incomplete application shall be summarily rejected and right to reject any or all the tenders including the lowest without assigning any reasons thereof is reserved.

Sd/-
DIRECTOR
MSME DEVELOPMENT INSTITUTE
MARGAO-GOIA

TENDER FORM

Government of India Ministry of MSME MSME DEVELOPMENT INSTITUTE Opp. Konkan Railway Station Quepem Road Margao-Goa			
Open Tender Notification No. MSME-DI/MAO/D-39011/1/2011-12			
Name of the work: Electrification of Mechanical Workshop			
<i>Note: If any columns left Blank, it will be considered as Zero (0)</i>			
Name and address of the Contractor			
Estimate			
Sl. No.	Particulars	Quantity	Quoted Rates (Amt in Rs.)
1	Design Supply, Installation, testing & Commissioning of Floor mounted outdoor type single front 10/14 SWG CRCA Steel construction, fully compartmentalized with separate busbar and cable chambers cable entry at bottom with glanding facilities and necessary mounting stand on 50 m.m. M.S. Angle with powder coated semans grey colour Electric Control Panel. <ul style="list-style-type: none"> • In the panel three nos. of chambers for 5 Kva capacitor • Incomer 200 Amps. Switch fuse unit TPN – 1 No. • 63 Amps. SFU – 5 Nos. TPN Insulator • 32 Amps. SFU – 7 Nos. TPN Insulator • 1 set RYB Lamp • 1 Ammeter with selector switch • 1 Voltmeter with Selector switch • 1 set 200 Amps 4 Pole Aluminum busbar covered with heat shrunk sleeves with colour coding • 1 stand mounted on 50 m.m. angle. • 2 Nos. 5 KVA Capacitor 	1 No.	
2	Supply, installation testing of lighting distribution Panel having 63 Amps. TPN MCB outgoing 10 Amps. MCB 10 Nos. with Metal encloser.	1 No.	
3	Supply Installation, testing High flow Crompton Greaves/ equivalent wall mounting fan	6 Nos.	
4	Single tubelight fittings Crompton make/equivalent	7 Nos.	
5	Supply installation testing 63 Amps. TPN Insulator with enclose L&T make /equivalent	2 Nos.	
6	Supply and installation 32 Amps. TPN with enclose L&T make /equivalent	5 Nos.	

7	15 Amps. Power switch socket Anchor make /equivalent	5 Nos.	
8	Supply, laying & termination 4 x 16 sq.mm. armed Aluminum cable laying through wall trench etc. – Policab make or equivalent.	Per Meter	
9	Supply, laying & termination 4 x 10 sq.mm. armed Aluminum cable laying through wall/trench etc. – Policab make or equivalent.	Per Meter	
10	Supply, laying & termination 3 x 4 sq.mm. armed Aluminum cable laying through wall trench etc. – Policab make or equivalent.	Per Meter	
11	Supply, laying & termination 2 x 2 sq.mm. armed Aluminum cable laying through wall trench etc. – Policab make or equivalent.	Per Meter	
12	Earthing complete, trench charcoal, salt, layer of mud as per electricity norms	2 Nos.	
13	Repairs and servicing of 400 watt HPMV Lamp	12 Nos.	
14	Disconnecting, removing existing pipe wiring, cleaning, re-servicing with 2 x 2 sq. mm. Al. cable per point.	Per Point	
15	Wiring for lighting, fan with 1.5 sq. mm. multi strand copper wire with switch, socket, etc.	Per Point	
16	Removing unwanted switch box, cable wiring.	1 job	
17	Disconnecting existing in coming cable, rerouting the cable to the Panel including termination, etc.	1 Job	